

MMQB-24-003 Attachment B Specifications

ROOFING

Common Name of Building: Pavilion #1

AASIS Asset Number: 120006497

Building Number: 55.17

GPS Coordinates Lat/Long: 35.1580,-90.7241

Contact Information: Superintendent: Vicki Trimble Email: vicki.trimble@arkansas.gov

Asst. Superintendent: William Wade Email: William.wade@arkansas.gov

Phone: 870.238.5217

Mailing Address: 201 CR 754, Wynne, AR 72396

Deliveries: Same

Specifications: For Shingle Roof

Contractor to Provide:

1. Contractor shall perform the removal of existing Shingles and Felt. And the removal of all debris from project site.
2. Contractor shall be responsible for all safety barriers to keep bystanders out of work areas and at a safe distance.
3. Contractor shall be responsible for any permits that maybe required.
4. Contractor shall remove skylights and frame in the openings and deck over with same thickness as rest of decking and on the inside ceiling skylight openings cover to best match material and finish. And if opening is deep may be able to picture frame and put a plastic diffuser. (Check with Greg Hart up front 501.554.9704)
5. Contractor shall furnish all materials, tools and labor, equipment to install new drip edge and StormTread synthetic roofing underlayment or equivalent and 30- year architectural shingles on roof Approx. (2'340 sq. ft.) of roof area. And Approx. (202' lin. Ft. drip edge) and Approx. (65' lin. Ft. vent ridge).
6. Contractor shall cut back decking and underlayment (approx.. 2" from center line of ridge for ventilation and to install new vent ridge).
7. The color of shingles shall best match existing and other roofs if close to the one that's being replaced.
8. Contractor shall install a premium starter strip around the eaves and rakes to help prevent wind uplift.
9. Contractor shall nail the shingles with a minimum one inch in length and a minimum four nails per shingle.

10. Contractor shall install the entire roof system to meet manufacturer's specifications and any state, county, and city building codes.
 11. Contractor shall install new roof vent boots/jacks. Roof vent boots & flashing to be painted color to best match roof.
 12. Contractor shall remove turbine vents if applicable and patch decking.
 13. Contractor shall be responsible for re-sealing all roof penetrations.
 14. Contractor shall be responsible for replacing any damage, rotten decking or fascia and drip edge lumber to match existing and the re-nailing of any loose decking or fascia.
 15. Any fascia, drip edge lumber removed or replaced contractor will caulk all joints and fill all nail holes and paint (Olympic Range Green in color Home Depot #SW 7750 must have a space between the SW and 7750 with two coats of BEHR Premium Plus Ultra paint and primer in one semi-gloss or equivalent.
 16. If any other paint is needed Greg Hart will be the one to give you the color codes to use.
 17. Contractor shall also be responsible to cover and protect anything that overspray or paint drips can possibly get on.
 18. Contractor shall also use an insecticide paint additive on final coat.
 19. Contractor shall work during normal business hours.
 20. Contractor shall be responsible for all materials delivered and protection of during construction.
 21. Contractor shall be responsible for the daily clean-up and the removal of all demolition/ construction debris including nails and metals offsite.
 22. Contractor shall be responsible for removing cable or satellite dishes and no dishes shall be attached to new shingle roof.
 23. Contractor shall install ice and water shield in all valleys and roof transitions.
 24. Photographs may be requested by Greg Hart during installation.
 25. Contractor shall be responsible for protection of building from elements during construction and the precautions to be taken to prevent damage to landscaping.
 26. Contractor shall remove and reinstall and protect all gutters and down spouts, if applicable.
 27. Park is not responsible for equipment and materials left on project site.
 28. All work to be done within (60 days) from time of bid being awarded.
 29. Contact Greg Hart 501.554.9704 once project is complete so final inspection can be completed.
- (SITE VISIT IS REQUIRED AND CONTRACTOR IS RESPONSIBLE FOR ALL ESTIMATES AND MEASUREMENTS BEING VERIFIED)

Make appointment with Park for site visit.