



# STATE OF ARKANSAS

## Division of Correction Office of Procurement

2403 E. Harding  
Pine Bluff, AR 71602

## ADDENDUM 1

TO: Vendors Addressed  
FROM: Flora Johnson  
DATE: April 7, 2021  
SUBJECT: ADC-21-C8785 Commercial Laundry Equipment and Supplies

The following change(s) to the above-referenced IFB have been made as designated below:

- ☒ Change of specification(s)  
☐ Additional document(s)  
☐ Change of bid opening time and date  
☐ Cancellation of bid  
☐ Other

### CHANGES TO SECTION 1.4 SPECIFICATIONS

- Remove the existing table and add the following revised table

Delivery Location	Laundry Equipment Industrial Strength Commercial	Capacity	Pad Size	Electrical	Additional Features Required
Benton Unit Maintenance 6701 Hwy 67 Bldg 60 Benton, AR 72015-8909	Commercial Dryer - Gas Heat	75-lb	No pad	208-240/60/3- phase	dual digital timer
Cummins Unit Maintenance Hwy 388 Grady, AR 71644	Washer- Extractor	80-lb	54" Deep; 54" Wide	208-240/60/3- phase	Rigid mount - final extract force of up to 200-Gs.
	Commercial Dryer - Steam Heat	120-lb	No pad	208-240/60/3- phase	dual digital timer

Delta Unit Maintenance 880 E. Gaines Dermott, AR 71638	Washer- Extractor	100 - 105-lb	No pad	220/240/60/3- phase	Rigid mount - final extract force of up to 200-Gs.
McPherson Unit Maintenance 302 Corrections Dr. Newport, AR 72112	Washer- Extractor	165-lb	No Pad	208/240/60/3- phase	Soft mount, final extract force of up to 350-Gs
	Commercial Dryer - Gas Heat	170-lb	No pad	208-240/60/3- phase	dual digital timer ;  Fire Suppression System w/12" air duct
Mississippi County W/R Maintenance 727 No. County Rd 599 Luxora, AR 72358	Washer- Extractor	65-lb	70" Wide; 44-3/4" Deep	208-240/60/3- phase	Rigid mount - final extract force of up to 400-Gs.
North Central Unit Maintenance 10 Prison Circle Calico Rock, AR 72519	Commercial Dryer - Steam Heat	120-lb	No pad	208-240/60/3- phase	Microprocessor control  Fire Suppression System
Ouachita River Unit Maintenance 100 Walco Lane Malvern, AR 72104	Washer- Extractor	220- 225 -lb	4'9" Deep; 5'9" Wide; 8' 1" tall	480/3-phase	Rigid mount - final extract force of up to 332-Gs.
Texarkana Reg. Corr Ctr Maintenance 305 E. 5th St Texarkana, AR 71854	Washer- Extractor	55 - 65-lb	No pad	240/60/3-phase	Soft mount, final extract force of up to 450-Gs.
	Commercial Dryer - Gas Heat;	75-lb	No pad	120/60/1-phase	dual digital timer
Tucker Unit Maintenance 2400 State Farm Rd Tucker, AR 72168	Washer- Extractor	100- 105-lb	45-1/2" X 36"	208-240/60/1- phase	Rigid mount, final extract force of up to 200-Gs.

Varner Unit Maintenance Hwy 388 Grady, AR 71644	Washer- Extractor	130-lb	50" Wide; 58" Deep; 78" High	440-480/60/3- phase	Rigid mount, final extract force of up to 200-Gs.
	Commercial Dryer - Steam Heat	120-lb	No pad	440-480/60/3- phase	microprocessor control

### CHANGES TO SECTION 1.7 INITIAL START-UP

- Add the following change to: Section 1.7 Initial Start-Up
  - A. ii. Providing items necessary to install and maintain Laundry Equipment (i.e., hardware fittings, connectors, hoses, etc.) as determined at the Site Visit and reduced to writing in Addendum 1.

The specifications by virtue of this addendum become a permanent addition to the above referenced IFB. Failure to return this signed addendum may result in rejection of your bid.

If you have any questions, please contact Flora Johnson at [flora.johnson@arkansas.gov](mailto:flora.johnson@arkansas.gov) or 870-850-8583.

Company: \_\_\_\_\_

Signature: \_\_\_\_\_

Date: \_\_\_\_\_