



STATE OF ARKANSAS

Division of Correction Office of Procurement

2403 E. Harding
Pine Bluff, AR 71602

ADDENDUM 2

TO: Vendors Addressed
FROM: Flora Johnson
DATE: April 8, 2021
SUBJECT: ADC-21-C8785 Commercial Laundry Equipment and Supplies

The following change(s) to the above-referenced IFB have been made as designated below:

- ☒ Change of specification(s)
- ☐ Additional document(s)
- ☐ Change of bid opening time and date
- ☐ Cancellation of bid
- ☐ Other

CHANGES TO SECTION 1.4 SPECIFICATIONS

- The electrical requirements for the Tucker Unit Washer-Extractor should be changed to 208-240/60/3-phase.
- Please delete the line items for the Washer/Extractors for the Ouachita River and the McPherson Units.
- See revised table below:

Delivery Location	Laundry Equipment	Capacity	Pad Size	Electrical	Additional Features Required
	Industrial Strength Commercial				
Benton Unit Maintenance 6701 Hwy 67 Bldg 60 Benton, AR 72015-8909	Commercial Dryer - Gas Heat	75-lb	No pad	208-240/60/3- phase	dual digital timer
Cummins Unit Maintenance Hwy 388 Grady, AR 71644	Washer- Extractor	80-lb	54" Deep; 54" Wide	208-240/60/3- phase	Rigid mount - final extract force of up to 200-Gs.

	Commercial Dryer - Steam Heat	120-lb	No pad	208-240/60/3- phase	dual digital timer
Delta Unit Maintenance 880 E. Gaines Dermott, AR 71638	Washer- Extractor	100 - 105-lb	No pad	220/240/60/3- phase	Rigid mount - final extract force of up to 200-Gs.
McPherson Unit Maintenance 302 Corrections Dr. Newport, AR 72112	Washer- Extractor	165-lb	No Pad	208/240/60/3- phase	Soft mount, final extract force of up to 350-Gs
	Commercial Dryer - Gas Heat	170-lb	No pad	208-240/60/3- phase	dual digital timer ; Fire Suppression System w/12" air duct
Mississippi County W/R Maintenance 727 No. County Rd 599 Luxora, AR 72358	Washer- Extractor	65-lb	70" Wide; 44-3/4" Deep	208-240/60/3- phase	Rigid mount - final extract force of up to 400-Gs.
North Central Unit Maintenance 10 Prison Circle Calico Rock, AR 72519	Commercial Dryer - Steam Heat	120-lb	No pad	208-240/60/3- phase	Microprocessor control Fire Suppression System
Quachita River Unit Maintenance 100 Walco Lane Malvern, AR 72104	Washer- Extractor	220- 225 -lb	4'9" Deep; 5'9" Wide; 8' 1" tall	480/3-phase	Rigid mount - final extract force of up to 332-Gs.
Texarkana Reg. Corr Ctr Maintenance 305 E. 5th St Texarkana, AR 71854	Washer- Extractor	55 - 65-lb	No pad	240/60/3-phase	Soft mount, final extract force of up to 450-Gs.
	Commercial Dryer - Gas Heat;	75-lb	No pad	120/60/1-phase	dual digital timer

Tucker Unit Maintenance 2400 State Farm Rd Tucker, AR 72168	Washer- Extractor	100- 105-lb	45-1/2" X 36"	208-240/60/3- phase	Rigid mount, final extract force of up to 200-Gs.
Varner Unit Maintenance Hwy 388 Grady, AR 71644	Washer- Extractor	130-lb	50" Wide; 58" Deep; 78" High	440-480/60/3- phase	Rigid mount, final extract force of up to 200-Gs.
	Commercial Dryer - Steam Heat	120-lb	No pad	440-480/60/3- phase	microprocessor control

CHANGES TO BID RESPONSE PACKET

- In the Bid Response Packet, please replace the Official Solicitation Price Sheet with Attachment 1.

The specifications by virtue of this addendum become a permanent addition to the above referenced IFB. Failure to return this signed addendum may result in rejection of your bid.

If you have any questions, please contact Flora Johnson at flora.johnson@arkansas.gov or 870-850-8583.

Company: _____

Signature: _____

Date: _____

OFFICIAL SOLICITATION PRICE SHEET

Attachment 1

#	Delivery Location	Laundry Equipment Industrial Strength Commercial	Capacity	Qty	Brand Name/Model Number	Total Cost
1	McPherson Unit 302 Corrections Dr. Newport, AR 72112	Commercial Dryer - Gas/Steam Heat	170 lb	1		\$
2	Texarkana Reg. Corr Ctr 305 E. 5th St Texarkana, AR 71854	Commercial Dryer - Gas/Steam Heat	75 lb	1		\$
3	Cummins Unit Hwy 388 Grady, AR 71644	Commercial Dryer - Gas/Steam Heat	120 lb	1		\$
4	Varner Unit Hwy 388 Grady, AR 71644	Commercial Dryer - Gas/Steam Heat	120 lb	1		\$
5	Benton Unit 6701 Hwy 67 Bldg 60 Benton, AR 72015- 8909	Commercial Dryer - Gas/Steam Heat	75 lb	1		\$
6	North Central Unit 10 Prison Circle Calico Rock, AR 72519	Commercial Dryer - Gas/Steam Heat	120 lb	1		\$
7	Cummins Unit Hwy 388 Grady, AR 71644	Washer-Extractor	80 lb	1		\$
8	Delta Unit 880 E. Gaines Dermott, AR 71638	Washer-Extractor	100- 105 lb	1		\$
9	Mississippi County W/R 727 No. County Rd 599 Luxora, AR 72358	Washer-Extractor	65 lb	1		\$
10	Texarkana Reg. Corr Ctr 305 E. 5th St Texarkana, AR 71854	Washer-Extractor	55 - 65 lb	1		\$

11	Tucker Unit 2400 State Farm Rd Tucker, AR 72168	Washer-Extractor	100 - 105 lb	1		\$
12	Varner Unit Hwy 388 Grady, AR 71644	Washer-Extractor	130 lb	1		\$
	TOTAL COST					\$

Per IFB item 1.11:

The agency requests delivery within 30 calendar days after receipt of the order. If this delivery date cannot be met, the Prospective Contractor **shall** state below the alternate number of days required to begin the service and/or place the commodity in the ordering agency's designated location. Failure to state the alternate delivery time obligates the Contractor to complete delivery by the agency's requested date. Extended delivery dates may be considered when in the best interest of the State.

Alternate Delivery: _____ **Days after receipt of order.**