

## MMQB-24-005 Attachment A Specifications

Common Name of Building: Admin

AASIS Asset Number: 120005674

Building Number: 14.04

GPS Coordinates Lat/Long: 34.2516,-93.1447

### Contact Information:

Asst. Superintendent: Brad DePriest

Email: brad.DePriest@arkansas.gov

Phone: 501.865.5812

Mailing Address: 2027 State Park Entrance Road, Bismarck, AR 71929

Deliveries: Same

### Specifications: For Shingle Roof

#### Contractor to Provide:

1. Prospective contractor shall perform the removal of existing Shingles and Felt. And the removal of all debris from project site.
2. Prospective contractor shall be responsible for all safety barriers like orange construction fence to keep bystanders out of work areas and at a safe distance or equivalent.
3. Prospective contractor shall be responsible for any permits that maybe required.
4. Prospective contractor shall remove the plywood at two low spots on back of the roof. Fix the low spots and replace the plywood and any bad or rotten wood, plywood, and re-nailing of any lose decking.
5. Prospective contractor shall furnish all materials, tools and labor, equipment to install new drip edge and StormTread synthetic roofing underlayment or equivalent and 30- year architectural shingles on roof Approx. (4'168 sq. ft. ) of roof area. And Approx. (270' lin. Ft. drip edge) and Approx. (84' lin. Ft. vent ridge) and Approx. 30' lin. Ft. endwall flashing.

6. Prospective contractor shall cut back decking and underlayment (approx. 2" from center line of ridge for ventilation and to install new vent ridge.
7. The color of shingles shall best match existing and other roofs if close to the one that's being replaced.
8. Prospective contractor shall install a premium starter strip around the eaves and rakes to help prevent wind uplift.
9. Prospective contractor shall nail the shingles with a minimum one inch in length and a minimum four nails per shingle.
10. Prospective contractor shall install the entire roof system to meet manufacturer's specifications and any state, county, and city building codes.
11. Prospective contractor shall install new roof vent boots/jacks. Roof vent boots & flashing, and chimney flashing to be painted color to best match roof.
12. Prospective contractor shall remove the power vent and put wire nuts on the wires and tape them and patch hole.
13. Prospective contractor shall cut two holes equal spaced and install two new Master flow 12" in. Weathered Wood Galvanized Steel Internally Braced Dual-Bearing Wind Roof Turbine vents or equivalent.
14. Prospective contractor shall be responsible for re-sealing all roof penetrations.
15. Prospective contractor shall remove and protect and reinstall all gutters and down spouts and is responsible for any damage to the gutters.
16. Prospective contractor shall be responsible for replacing all fascia (Approx. 270' lin. Ft.) and drip edge lumber with new LP SmartSide fascia cedar texture ¾" thick by same width as existing and a sub-fascia may have to be added to keep fascia straight and not wavy.
17. All fascia, drip edge lumber replaced contractor will caulk all joints and fill all nail holes and paint (Olympic Range Green in color Home Depot #SW 7750 must have a space between the SW and 7750 with two coats of BEHR Premium Plus Ultra paint and primer in one semi-gloss or equivalent.
18. If any other paint is needed Greg Hart will be the one to give you the color codes to use.
19. Prospective contractor shall also be responsible to cover and protect anything that overspray or paint drips can possibly get on.
20. Prospective contractor shall also use an insecticide paint additive on final coat.
21. Prospective contractor shall work during normal business hours.
22. Prospective contractor shall be responsible for all materials delivered and protection of during construction.
23. Prospective contractor shall be responsible for the daily clean-up and the removal of all demolition/ construction debris including nails and metals offsite.

24. Prospective contractor shall be responsible for removing cable or satellite dishes and no dishes shall be attached to new shingle roof.
25. Prospective contractor shall install ice and water shield in all valleys and roof transitions.
26. Photographs may be requested by Greg Hart during installation.
27. Prospective contractor shall be responsible for protection of building from elements during construction and the precautions to be taken to prevent damage to landscaping.
28. Prospective contractor shall remove and reinstall and protect all gutters and down spouts, if applicable.
29. Park is not responsible for equipment and materials left on project site.
30. All work to be done with in (60days) from time of bid being awarded.
31. Contact Greg Hart 501.554.9704 once project is complete so final inspection can be completed.

(SITE VISIT IS REQUIRED AND CONTRACTOR IS RESPONSIBLE FOR ALL ESTIMATES AND MEASUREMENTS BEING VERIFIED)

Make appointment with Park for site visit.